

# **PVMaT Advances in the Photovoltaic Industry and the Focus of Future PV Manufacturing R&D**

**Preprint**

Richard L. Mitchell and C. Edwin Witt  
*National Renewable Energy Laboratory*

Richard King  
*U.S. Department of Energy*

Douglas Ruby  
*Sandia National Laboratories*

*To be presented at the 29<sup>th</sup> IEEE PV Specialists Conference  
New Orleans, Louisiana  
May 20-24, 2002*



**NREL**

**National Renewable Energy Laboratory**

1617 Cole Boulevard  
Golden, Colorado 80401-3393

NREL is a U.S. Department of Energy Laboratory  
Operated by Midwest Research Institute • Battelle • Bechtel

Contract No. DE-AC36-99-GO10337

## NOTICE

The submitted manuscript has been offered by an employee of the Midwest Research Institute (MRI), a contractor of the US Government under Contract No. DE-AC36-99GO10337. Accordingly, the US Government and MRI retain a nonexclusive royalty-free license to publish or reproduce the published form of this contribution, or allow others to do so, for US Government purposes.

This report was prepared as an account of work sponsored by an agency of the United States government. Neither the United States government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States government or any agency thereof.

Available electronically at <http://www.osti.gov/bridge>

Available for a processing fee to U.S. Department of Energy  
and its contractors, in paper, from:

U.S. Department of Energy  
Office of Scientific and Technical Information  
P.O. Box 62  
Oak Ridge, TN 37831-0062  
phone: 865.576.8401  
fax: 865.576.5728  
email: [reports@adonis.osti.gov](mailto:reports@adonis.osti.gov)

Available for sale to the public, in paper, from:

U.S. Department of Commerce  
National Technical Information Service  
5285 Port Royal Road  
Springfield, VA 22161  
phone: 800.553.6847  
fax: 703.605.6900  
email: [orders@ntis.fedworld.gov](mailto:orders@ntis.fedworld.gov)  
online ordering: <http://www.ntis.gov/ordering.htm>



# PVMaT ADVANCES IN THE PHOTOVOLTAIC INDUSTRY AND THE FOCUS OF FUTURE PV MANUFACTURING R&D

Richard L. Mitchell,<sup>1</sup> C. Edwin Witt,<sup>1</sup> Richard King,<sup>2</sup> Douglas Ruby<sup>3</sup>

<sup>1</sup> National Renewable Energy Laboratory, Golden, CO; <sup>2</sup> U.S. Department of Energy, Washington, D.C.; and

<sup>3</sup> Sandia National Laboratories, Albuquerque, NM

## ABSTRACT

The DOE Photovoltaic Manufacturing Technology (PVMaT) Project has conducted cost-shared manufacturing R&D with the photovoltaic industry for over 10 years. During this time, research has focused on the project's stated objectives of improving photovoltaic manufacturing processes and products, lowering manufacturing costs, and providing a foundation for the scale-up of U.S. photovoltaic (PV) manufacturing. Progress made by each of the U.S. PV industry participants in this project has resulted in a significant reduction in the industry's direct PV module-manufacturing costs and an impressive scale-up in U.S. PV manufacturing capacity. The majority of the efforts have been module related. Results in terms of automation, yield, and throughput have provided a significant reduction in direct manufacturing costs. Cost reductions and capacity increases resulting from these efforts are discussed.

## INTRODUCTION

The PVMaT Project was initiated in 1990 to assist the U.S. PV industry in extending its world leadership role in PV manufacturing and advancing the commercial development of PV modules and systems. As previously described [1-15], Photovoltaic Manufacturing R&D is a government/industry R&D partnership between the federal government (through the U.S. Department of Energy [DOE]) and members of the U.S. PV industry. Photovoltaic Manufacturing R&D is designed to accomplish its purpose by helping industry improve manufacturing processes, accelerate manufacturing cost reductions for PV modules, improve commercial product performance, and lay the groundwork for a substantial scale-up in the capacity of U.S.-based PV manufacturing plants.

PVMaT has been carried out as six initial and separate phases designed to address separate R&D requirements. These are Phases 1, 2A, 2B, 3A, 4A, and 5A. A description of the focus and accomplishments for FY 1991 phase 1 solicitation, FY 1992 2A solicitation, FY 1992 3A solicitation, FY 1993 2B solicitation, FY 1995 4A solicitation, and FY 1998 5A solicitation have been detailed in previous papers [1-15]. The research under the 14 subcontracts awarded under the 5A solicitation, Product-Driven Manufacturing, were divided into two categories, 5A1 and 5A2 (shown in Tables 1 and 2). The objectives of these subcontracts included: (5A1) PV System and Component Technology —

manufacturing improvements directed toward innovative, low-cost, high-return, high-impact PV products, with subcontracted efforts addressing manufacturing R&D generally related to PV system components and aspects other than modules; and (5A2) PV Module Manufacturing Technology — improvements in module-manufacturing processes and the manufacturing, assembly, and integration of systems to build a PV product, as well as the packaging of that product to meet market requirements. Progress under these subcontracts is described in several papers in these proceedings.

## STATUS

The PV manufacturers participating in the PVMaT research subcontracts awarded in 1998 have just completed their research. Improvements were made in module manufacturing and other areas, including power conditioning, system design, and encapsulation. The majority of the subcontract efforts under this solicitation — over 85% — were in module manufacturing. The major areas addressed by thin-film manufacturers included deposition processes, deposition rates, yield, and ES&H issues. The research carried out by crystalline silicon manufacturers generally related to better automation, yield, throughput, and ES&H considerations. Advances in both of these areas have provided a significant reduction in direct manufacturing costs for the U.S. PV industry.

Table 1. 5A2 PV Module Manufacturing Subcontractors.

ASE Americas	Cost Reductions in High Volume EFG PV Module Manufacturing Line
AstroPower, Inc.	Silicon-Film™ Solar Cells by a Flexible Manufacturing System
BP Solar	Improvements in Polycrystalline Silicon PV Module Manufacturing Technology
Energy Conversion Devices	Efficiency and Throughput Advances in Continuous Roll-to-Roll a-Si Alloy Manufacturing Technology
Evergreen Solar	Continuous, Automated Manufacturing of String Ribbon Si PV Modules
First Solar, LLC	Specific PVMaT R&D in CdTe Product Manufacturing
Global Solar Energy	Manufacturing Cost and Throughput Improvements for CIGS-based Thin Film PV Modules
Siemens Solar Industries	Specific PVMaT R&D on Siemens Cz Silicon Product Manufacturing

Table 2. 5A1 Product-Driven System and Component Subcontractors.

Crystal Systems	Production of Solar Grade (SoG) Silicon by Refining of Liquid Metallurgical Grade (MG) Silicon
Omnion	Manufacturing and System Integration Improvements for One- and Two-Kilowatt Residential PV Inverters
PowerLight Corp.	PowerGuard® Advanced Manufacturing
Schott-Applied Power Corp., Ascension Division	Cost Reduction and Manufacture of the Sunline AC Module
Spire Corp.	Post-Lamination Manufacturing Process Automation for Photovoltaic Modules
Utility Power Group – Kyocera Solar	Development of a Fully Integrated PV System for Residential Applications

An additional FY2001 solicitation, "PV Manufacturing R&D - In-Line Diagnostics and Intelligent Processing in Scale-Up Manufacturing," was issued on August 7, 2000. On October 9, 2000, 22 proposals were received in response to this solicitation. These research proposals were divided into two areas: Category A1, PV System and Component Technology; and Category A2, PV Module Manufacturing Technology. These proposals [6 under category A1 and 16 under Category A2, with an emphasis In-Line Diagnostics and Intelligent Processing] have been evaluated and subcontracts are currently being awarded.

**PROGRESS IN COST REDUCTION AND CAPACITY INCREASES**

Direct module-manufacturing costs and individual plant capacity data have been collected annually by the PVMaT Project in an attempt to quantify the impact of the technical improvements under the module manufacturing R&D [3-9].




Fig. 1. PVMaT manufacturing cost/capacity (2001 data using 2001 dollars).

These most recent cost and capacity data, shown in Fig. 1, represent an update of previous projections regarding these subcontracted efforts. Data in this figure are based on the manufacturer's maximum production capacity (in MW) during a given year for each of the 13 active manufacturing

lines. As in previous years, several large manufacturers reported that they have dedicated a portion of their production lines to cell production for shipment to other locations for module fabrication. This aspect of PV production is included in the PVMaT capacity calculations. The "average" module-manufacturing cost represents the average cost per watt of modules (weighted by each participant's capacity of both cells and modules presented in FY 2001 dollars) for these 13 PVMaT industrial participants. Module cost estimates are based on each manufacturer's module-production capacity level and include only those costs directly associated with the manufacturing of modules (i.e., no costs from marketing, administration, or sales). It should be noted that the data associated with any particular point in time represent a potential capability. Actual manufacturing-production levels may be less (and concomitant costs higher) due to other considerations such as market conditions or available labor. Fig. 1 shows that the total FY 2001 module-manufacturing capacity (including cells for later module fabrication) has grown by a factor of 13 in the last 10 years to 176 megawatts (MW). In addition, the weighted-average direct manufacturing cost for these companies has decreased over the last 10 years by about 45%, to \$2.46. The industry also projects an additional 50% reduction in cost and an 82% increase in capacity by the year 2007.

As in previous years, 2001 cost/capacity data provided by the active PVMaT manufacturers represent several modifications to their previous projections. Even though optimism in cost/capacity data always increases the further out into the future one stretches the projections, cost/capacity projections have historically been fairly realistic for mature manufacturing centers for up to 3 years out. Since the "average" module-manufacturing cost is weighted by each participant's capacity, these larger, more mature manufacturing centers help stabilize the level of these projections. By 2004, these projections by the PV industry indicate module-manufacturing costs of \$1.46/Wp (a 68% reduction from 1992 levels) and a production capacity increase to 562.5 MW (40 times the 1992 level for PVMaT industrial participants).

**COMPARISON THIN-FILM AND NON-THIN-FILM COST REDUCTION AND PRODUCTION RATIOS**

An analysis of the FY 2001 module-manufacturing cost and capacity data has also allowed a comparison between the thin-film and non-thin-film module manufacturers. Fig. 2 presents the cost/capacity data collected in FY 2001 for the non-thin-film manufacturers, and shows their module-manufacturing capacity (including cells for later module fabrication) has grown by a factor of 12 in the last 10 years, whereas their "average" cost for manufacturing PV modules has been reduced by more than 51%. Similarly, Fig. 3 presents the cost/capacity data collected in FY 2001 for the thin-film manufacturers, and shows their module-manufacturing capacity has grown by a factor of 25 during this time, whereas their "average" cost for manufacturing PV modules has been reduced by more than 64%. As can be seen, the majority of the cost reduction for the thin-film

manufacturers has taken place prior to 1999, and the majority of the capacity increase has been in the last 2 years.




Fig. 2. Non-thin-film PVMaT manufacturing cost/capacity (2001 data using 2001 dollars).




Fig. 3. Thin-film PVMaT manufacturing cost/capacity (2001 data using 2001 dollars).




Fig. 4. PVMaT thin-film/non-thin-film production ratios.

A comparison of the historical and projected production level data for the PVMaT industrial participants' active manufacturing lines is presented in Fig. 4. These data indicate a significant increase planned for the ratio of production over the next 3-5 years. This represents a combination of the aggressive expansion and emergence of thin films into the market, as well as the optimistic projections of newer manufacturing centers.

### RECAPTURE OF RESEARCH FUNDING

To gain an additional measure of the benefits from PV manufacturing research, we compared the funding invested in module-manufacturing subcontracts with the estimated economic benefits to the customers (e.g., reduced prices) and/or to the manufacturers (e.g., increased profits or increased available investment capital). We have collected estimates of savings (i.e., reduced costs) directly attributable to specific research accomplishments under the PV Manufacturing R&D project and how each industrial partner will distribute these savings between themselves and their customers. By comparing the savings to the customers with the government investment (the "Public" curve) and the companies' savings with their cost-share investment ("Industry" curve), we have derived Fig. 2. Dollars saved and dollars invested are calculated yearly (in FY 2001 dollars) on a to-date cumulative basis, and the ratios are plotted in percentages. It is obvious the benefits of the project are much more than the investment, with the module-manufacturing R&D funding being recaptured prior to 1999. The data in Fig. 2 are only based on the PVMaT funding directed at module manufacturing, which represents more than 85% of the total project funds. One can see that even if the additional 15% of the project funding that was directed toward BOS and systems research were included in the recapture calculations, it would not have a significant impact on the outcome, and that the project as a whole is more than paying for itself.




Fig. 5. Recaptured PVMaT project module funding (2001 data using 2001 dollars).

## CONCLUSIONS

The PV Manufacturing R&D project has just completed the last year of the 1998 subcontracted activities. Subcontracts resulting from proposals received in response to the most recent PV Manufacturing R&D procurement for In-Line Diagnostics and Intelligent Processing are currently being awarded. At this time, it is apparent from Fig. 1 that the U.S. PV industry involved in the PV Manufacturing R&D project has made significant progress toward reducing manufacturing costs and increasing PV module-manufacturing capacity. In the last 10 years, "average" module-manufacturing costs (FY 2001 dollars) have been reduced by more than 45%, and total manufacturing capacity for the 13 PV Manufacturing R&D industrial participants has grown by a factor of 13. By 2004, projections by the PV industry indicate module-manufacturing costs of \$1.46/Wp (a 68% reduction from 1992 levels) and a production capacity increase to 562.5 MW (40 times the 1992 level for PVMaT industrial participants). There are continued indications, in both the industry's future cost/capacity data and its technical projections, that near-term progress in these areas has been significant and that the long-term optimism for continuing improvements from PV Manufacturing R&D is high.

## ACKNOWLEDGMENTS

This work is supported under DOE Contract No. DE-AC36-83CH10093 with NREL. Many people have contributed to the development and implementation of the Photovoltaic Manufacturing R&D project and to the R&D efforts carried out therein. The authors recognize that this paper represents their work.

## REFERENCES

- [1] C.E. Witt, L.O. Herwig, R. Mitchell, and G.D. Money, "Status of the Photovoltaic Manufacturing Technology (PVMaT) Project," *Proceedings of the 22nd IEEE Photovoltaics Specialists Conference*, Las Vegas, Nevada, October 1991.
- [2] C.E. Witt, R.L. Mitchell, G.D. Money, and L.O. Herwig, D. Hasti, and R. Sellers, "Progress in Phases 2 and 3 of the Photovoltaic Manufacturing Technology Project (PVMaT)," *Proceedings of the 23rd IEEE Photovoltaics Specialists Conference*, Louisville, Kentucky, May 1993.
- [3] C.E. Witt, L.O. Herwig, R.L. Mitchell, H.P. Thomas, R. Sellers, and D.S. Ruby, "Recent Progress in the Photovoltaic Manufacturing Technology Project (PVMaT)," *Proceedings of the 1st World Conference on Photovoltaics*, Waikoloa, Hawaii, December 1994.
- [4] R.L. Mitchell, C.E. Witt, H.P. Thomas, L.O. Herwig, D.S. Ruby, and C.C. Aldrich, "Benefits from the U.S. Photovoltaic Manufacturing Technology Project," *Proceedings of the 25th IEEE Photovoltaics Specialists Conference*, Washington, D.C., May 1996.
- [5] R.L. Mitchell, C.E. Witt, H.P. Thomas, "Photovoltaic Manufacturing Technology (PVMaT) Project - Latest Results," *Proceedings of the NREL/SNL Photovoltaic Program Review Meeting*, Lakewood, Colorado, November 1996.
- [6] R.L. Mitchell, C.E. Witt, H.P. Thomas, L.O. Herwig, D.S. Ruby, Richard King and C.C. Aldrich, "Progress Update On The U.S. Photovoltaic Manufacturing Technology Project," *Proceedings of the 26th IEEE Photovoltaics Specialists Conference*, Anaheim, CA, October 1996.
- [7] C.E. Witt, R.L. Mitchell, M. Symko-Davies, H.P. Thomas, R. King, and D.S. Ruby, "Current Status and Future Prospects for the PVMaT Project," *Presented at 11th International Photovoltaic Science and Engineering Conference*, Sapporo Japan, September 1999.
- [8] C.E. Witt, R.L. Mitchell, M. Symko-Davies, H.P. Thomas, R. King, and D.S. Ruby, "Ten Years of Manufacturing R&D in PVMaT - Technical Accomplishments, Return on Investment, and Where Do We Go Next," *Proceedings of the 28th IEEE Photovoltaics Specialists Conference*, Anchorage, Alaska, September 2000.
- [9] C.E. Witt, T. Surek, R.L. Mitchell, M. Symko-Davies, and H.P. Thomas, "Terrestrial Photovoltaics Technologies - Recent Progress in Manufacturing R&D", *Presented at the ASME 2000 34th National Heat Transfer Conf.*, Pittsburgh, Pennsylvania, August 2000.
- [10] C.E. Witt, R.L. Mitchell, H.P. Thomas, M.L. Symko, R. King, and D.S. Ruby, "Manufacturing Improvements in the Photovoltaic Manufacturing Technology (PVMaT) Project," *Proceedings of the 2nd World Conference on Photovoltaic Solar Energy Conversion*, Vienna, Austria, July 1998.
- [11] R.L. Mitchell, M.L. Symko, H.P. Thomas, and C.E. Witt, "PVMaT 1998 Overview," *Presented at the NCPV Photovoltaic Program Review Meeting*, Denver, Colorado, September 1998.
- [12] M. Symko-Davies, R.L. Mitchell, C.E. Witt, H.P. Thomas, R. King, and D.S. Ruby, "Decade of PV Industry R&D Advances in Silicon Module Manufacturing," *Proceedings of the 28th IEEE Photovoltaics Specialists Conference*, Anchorage, Alaska, September 2000.
- [13] W. Bower, H.P. Thomas, B. Kroposki, R. Bonn, and T. Hund, "Balance-of-System Improvements for Photovoltaic Applications Resulting from the PVMaT 4A1 Program," *Proceedings of the 26th IEEE Photovoltaics Specialists Conference*, Anaheim, CA, October 1996.
- [14] H.P. Thomas, B. Kroposki, P. McNutt, C.E. Witt, W. Bower, R. Bonn, and T.D. Hund, "Progress in Photovoltaic System and Component Improvements," *Proceedings of the 2nd World Conference on Photovoltaic Solar Energy Conversion*, Vienna, Austria, July 1998.
- [15] H.P. Thomas, B. Kroposki, C.E. Witt, and W. Bower, "Progress in Photovoltaic Components and Systems," *Presented at the 16th European Photovoltaic Solar Energy Conference and Exhibition*, Glasgow, Scotland, U.K., May 2000.

# REPORT DOCUMENTATION PAGE

Form Approved  
OMB NO. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE May 2002	3. REPORT TYPE AND DATES COVERED 29 <sup>th</sup> IEEE PVSC-Conference Paper May 20-24, 2002	
4. TITLE AND SUBTITLE PVMaT Advances in the Photovoltaic Industry and The Focus of Future PV Manufacturing R&D			5. FUNDING NUMBERS PVP26101	
6. AUTHOR(S) R.L. Mitchell, <sup>1</sup> C.E. Witt, <sup>1</sup> R. King, <sup>2</sup> and D. Ruby <sup>3</sup>				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) 1. National Renewable Energy Laboratory, Golden,CO 2. Department of Energy, Washington, DC 3. Sandia National Laboratories, Albuquerque, NM			8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) National Renewable Energy Laboratory 1617 Cole Blvd. Golden, CO 80401-3393			10. SPONSORING/MONITORING AGENCY REPORT NUMBER  NREL/CP-520-31436	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION/AVAILABILITY STATEMENT National Technical Information Service U.S. Department of Commerce 5285 Port Royal Road Springfield, VA 22161			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words): This conference paper describes the DOE Photovoltaic Manufacturing Technology (PVMaT) Project which has conducted cost-shared manufacturing R&D with the photovoltaic industry for over 10 years. During this time, research has focused on the project's stated objectives of improving photovoltaic manufacturing processes and products, lowering manufacturing costs, and providing a foundation for the scale-up of U.S. photovoltaic (PV) manufacturing. Progress made by each of the U.S. PV industry participants in this project has resulted in a significant reduction in the industry's direct PV module-manufacturing costs and an impressive scale-up in U.S. PV manufacturing capacity. The majority of the efforts have been module related. Results in terms of automation, yield, and throughput have provided a significant reduction in direct manufacturing costs. Cost reductions and capacity increases resulting from these efforts are discussed.				
14. SUBJECT TERMS: PV; PVMaT; PV industry; manufacturing R&D; future; costs; capacity; modules; automation; yield; throughput			15. NUMBER OF PAGES	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT  UL	