



Radical Re-Envisioning of Data Centers with Row-Integrated Fuel Cells

November 7, 2019

Fuel Cell Seminar, Long Beach, California

G. Saur¹, S. Hammond¹, J. Kurtz¹(Presenter), T. Cader²,

D. Thoss³, S. Ecker³, R. L. Mount⁴, R. S. Mount⁴, C.

Skidmore⁴

- ¹ National Renewable Energy Laboratory
- ² Hewlett Packard Enterprise
- ³ Daimler AG
- ⁴ Power Innovations



Renewables

Renewable electricity (direct and region specific simulation)

Production

Hydrogen production via electrolysis in grid connect, grid service, and direct renewable operation modes

Storage

Gaseous storage >300 kg

Distribution

Hydrogen pipeline traverses ESIF from north end (hydrogen production, compression, and storage) to data center

Data Center

Fully integrated and operational (~May 2019)

Partner-Driven Proof of Concept

Long-Term Vision Research

Industry Partners & NREL

Industry Partners

System concepts, scenarios, economics Integrated FC/IT rack proof-ofconcept

Business plan, customers, & products




'm honored to have been a guest at National Renewable Energy Laboratory Partner Week, speaking with other organizations about the role and importance of innovation. As the demands placed on data centers increases, putting strain on the availability of power and its cost there is a growing need for more sustainable solutions. Thanks to our continued partnership, Hewlett Packard Enterprise and National Renewable Energy Laboratory are pioneering the use of hydrogen fuel cells to create carbon free data centers with better power delivery,



- > HPE
- Daimler
- Power **Innovations**
- > NREL

Data Center Energy Challenge –

High costs in power infrastructure, inefficiencies, and backup power required



^{*} http://www.nrdc.org/energy/data-center-efficiency-assessment.asp

Carbon-Free Data Center Scale Comparison – Megawatts Shipped




Figure 2: Megawatts of Fuel Cells Shipped Worldwide by


Application

Source: U.S. Department of Energy Fuel Cell Technologies Office, E4 Tech


https://energy.gov/sites/prod/files/2017/10/f37/fcto_2016_market_report.pdf

Just one large data center is ~25% of worldwide stationary shipments (MW) in 2016

Carbon-Free Data Center Vision



Pipeline Connecting Hydrogen and the Data Center




Hydrogen in NREL's Data Center

Advantages

- Potential to lower up-front capital costs
 - Eliminate traditional power distribution and conversion
 - Negate need for back-up generators and traditional UPS
 - Reduce expensive copper wiring
- Reduce and re-use thermal load
 - Reduce power electronic heat loads
 - PEM FC connected to water loop



FC System Components



Demonstration Results and Lessons Learned

System shake-out and testing began May 2019


Test Matrix

- Performance data of the system in different situations
- Range of back-up and primary power scenarios
- Demonstrate automotive fuel cell in stationary application

Test name	Test Time (hr)
High power	6
Transient	6
Low power	4
Ramp (Results follow)	2
Start/stop	6
Soak Test I - Weekend	5
Soak Test II - 2 week	5
Endurance Test I - Low Power	18
Endurance Test II - High Power	18

Lessons Learned 1

Wireless safety system not likely solution going forward; wired systems more reliable




- Unexpected loss of permission to run fuel cell
 - System handled unexpected scenario well
 - Battery took over as load was shed
 - House power (future: redundant fuel cell) took over load
- Wireless remote watchdog causing problems
 - RF interference in data center causing wireless systems to intermittently time-out
- Moved antenna outside; resolved for now

Lessons Learned 2

Successful Ramp Test

Next up: Shake-out of other test protocols



- > Fuel cell provides power for system
 - IT rack, battery, auxiliary equipment
- > PEM fuel cell can ramp closely to load
 - Allow smaller battery subsystems than typical UPS
- > IT load maintained 10 kW-40 kW for duration of test
 - System switched seamlessly between house line power and FC system with no impact to load on IT rack
 - Load ramped ~6.6% of max every 3 min

Main takeaways:

- The first steps to scaleup to large data centers (20 MW+, 24/7 operation), while a challenge, are currently being tested
- Safety systems need to provide branch isolation and failure management for paralleled fuel cell systems

Exhaust vent now insulated to reduce condensation/water back flow problem; alternate condensate systems installed*



Two demonstrations being tested, a 70-kW system at NREL and a 250-kW system at Power Innovations.

- Testing and shake-out providing valuable data
- Systems have been safe even in unexpected events
- Learning new ways to improve system dynamics and support systems
- * Water recovery can be an important consideration. Future improvement could be separating the negative safety pressure fan from the water exhaust.

Benefits of Fuel Cell-Powered Data Center

- Savings from grid independent operation
 - On-site generation with behind the meter electricity price
 - Avoid demand charges
 - FC electric power directly used by computer for low power usage effectiveness (PUE)
 - Stable load and controlled environment favor higher fuel cell efficiency and longer servicer life.
- Energy savings:
 - Overall efficiency with heat recovery to drive chiller for building heating and equipment cooling needs
 - Data center of low cost and small footprint by FC racks
 - No H₂ distribution cost needed as H₂ is consumed locally
- Increase fuel cell production and accelerate its deployment.

Summary

Holistic Vision

- Conceptual models for size, performance, and economic estimates
- Economically viable nearterm option includes natural gas
- Lowest up-front costs may not be lowest total cost of ownership options

Product Acceleration

- Verify proof-of-concept in a functional data center
- Identify codes and standards for hydrogen fuel cells in data centers
- Automotive fuel cell in a new application => increase quantity and decrease cost
- Partners include product developers and end users

What's Next

- Identify systematic solutions for challenges
- Refine and define system
- Improve estimates
- Validate system and install at scale
- Will continue to work closely with DOE in detailing improvements for stationary H2 FC for data centers.

With the sustained drop of the cost for renewable power, long-term renewable hydrogen to supply fuel cells for powering a data center can realize both decarbonization and economic returns.

Acknowledgements also to the following for support of the project:

K. Regimbal,¹ D. Sickinger,¹ R. Fraley,¹ O. Smith,¹ M. Mann,¹ M. Ruple,¹ S. Gilleon,¹ J. Izquierdo,² J. Ladra,³ P. Muench,³ D. Papageorgopoulos,⁴ N. Stetson⁴

- ¹ National Renewable Energy Laboratory
- ² Hewlett Packard Enterprise
- ³ Daimler AG
- ⁴ U.S. Department of Energy

Thank You

www.nrel.gov

NREL/PR-5400-75401

This work was authored in part by the National Renewable Energy Laboratory, operated by Alliance for Sustainable Energy, LLC, for the U.S. Department of Energy (DOE) under Contract No. DE-AC36-08GO28308. Funding provided by U.S. Department of Energy Office of Energy Efficiency and Renewable Energy Fuel Cell Technologies Office. The views expressed in the article do not necessarily represent the views of the DOE or the U.S. Government. The U.S. Government retains and the publisher, by accepting the article for publication, acknowledges that the U.S. Government retains a nonexclusive, paid-up, irrevocable, worldwide license to publish or reproduce the published form of this work, or allow others to do so, for U.S. Government purposes.

