Megawatt-Scale Low Temperature Electrolyzer Research Expansion

D. Leighton, K. Hartmann, V. Singh, and K. Hurst; National Renewable Energy Laboratory

OVERVIEW

- · Support industry partners participating in the \$1B DOE Clean Hydrogen Electrolysis Program
- · Expand ARIES capability at NREL's Flatirons Campus to flexibly operate multi-MW scale low-temperature electrolyzers
- PEM stacks from 0.5-6 MW scale, liquid alkaline stacks from 0.5-2 MW scale
- Liquid alkaline stacks with "core" balance of plant provided at 0.5-6 MW scale
- . Flexible for simultaneous operation of stacks to 6 MW
- aggregate · PEM or liquid alkaline full system integration up to
- 10 MW · Grid integration with ARIES assets including renewables
- · Commissioning 3 years from start

POTENTIAL IMPACT


- Development and installation of a flexible low-temperature electrolyzer research capability at the multi-MW scale with integrated renewables de-risks field deployments on the 10+ MW scale
- This NRFL capability:
- · Helps lower the cost barrier to entry for electrolyzer manufacturers needing system and stack evaluation
- · Enables more electrolyzer manufacturers to accelerate to commercialization with building block scale demonstration and validation
- . DOE HFTO investment to support the \$1B DOE Clean Hydrogen Electrolysis Program working to achieve the Hydrogen Shot goal of \$1 for 1 kg hydrogen in 1 decade. lower greenhouse gas emissions and criteria pollutants. build clean energy infrastructure, and provide pathways to private sector uptake

SUMMARY

- New project to develop a flexible multi-MW low-temperature electrolysis experimental platform on the 0.5 - 10 MW scale . Flexibly designed balance of plant and balance of system to
- meet most PEM and liquid alkaline stack designs · Connection to current and future hydrogen infrastructure at
- NREL's Flatirons Campus, as well as the renewable production assets (research grids)
- · This capability will fill a critical industry need for multi-MW scale electrolyzer stack and system performance validation, including renewables coupling




APPROACH Integration with Existing ARIES Platform



This new low-temperature electrolyzer capability will be integrated with exiting hydrogen, electrical, and renewable production assets at NREL's Flatirons Campus

Preliminary Layout Visualization




This preliminary layout diagram shows the critical building blocks of the planned multi-MW electrolyzer research capability. The upcoming detailed design phase will further refine container access, system connection points stack in/out flexibility, and optimize the design.


System Sizing Boundaries



This NREL capability will have all the balance of system or plant needed to support the equipment delivered by the stack manufactures for evaluation. The delivered equipment could range from a single stack to a full system

Process Flow Diagram





Configurable cable tray design for independent, serialization, or parallelization of PSU "Building Blocks" to meet current and voltage needs of multiple multi-MW stacks. Actual configuration depends on stack technical specifications and PSU canabilities

hydrogen site)

ACCOMPLISHMENTS AND **PROGRESS**

- · This is a newly awarded project that has been in progress less than six months
- · The focus of work so far has been scoping, design, budgeting, and identification of long lead components ("approach" section)
- Highlighted to the right is progress made on infrastructure upgrades needed to enable this research capability

Permanent Site Construction Contracting Underway



auxiliary requirements to support MW-scale electrolysis research. See presentation TA048 Leighton for more details on current site design

Campus Electrical Infrastructure Upgrades Funded



gear and conduit for 10 MW (everything but hydrogen system transformer and wiring)

One-Line Drawing

The one-line drawing highlights the new hardware components which are needed for the

planned multi-MW electrolyzer research capability and how the new hardware is planned

Campus Water Supply Infrastructure

Upgrades Funded

Senarate infractructure investment will develop water main from recervoir

treatment facility, storage system, and supply lines to equipment (including

to integrate into the exiting hydrogen system at NREL's Flatirons Campus.

DC Electrical Architecture

- - · Campus construction projects for upstream electrical infrastructure upgrades and water supply system are
- Emerging stack technologies (different current/voltage) combinations, footprints, etc.)
 - Flexible DC electrical infrastructure design using ~1 MW "building blocks" to maximize voltage/current
 - · Flexible balance of plant design to support different
 - size stacks and system specifications

COLLABORATION AND COORDINATION

· This work is directly funded by HFTO with separate

treatment, upstream electrical, etc.)

- · The project will be integrated into the ARIES platform at NREL's Flatirons Campus
- Gathering inputs from numerous PEM and Alkaline manufacturers for technical specifications (voltage, current, etc.) to maximize flexibility to accept a range of manufacturer's electrolyzers, both current and future
 - · Additional inputs welcome!

FUTURE WORK

- · Initiate detailed design phase
 - · Identify, specify, and order long lead time items · Determine the optimal deployment configuration and
 - subsystem sizina · Identify system capability boundaries and collaborate
- with industry to align with industry needs Develop timeline for purchase, installation, and
- commissioning of critical items to achieve successful deployment
- Work with NREL's site operations team to coordinate
- · Begin assembly of custom balance of plant and balance of system for PEM and liquid alkaline electrolyzers

- Timeline (supply chain issues, equipment availability, etc.)
 - · Site construction is moving forward now
 - Planning to build containerized sub-systems in parallel with site construction and lift into place and integrate after construction completion
 - . Order major, long-lead equipment as quickly as possible to progress critical path
 - funded and are nearing completion of design phases
 - combinations

 - . Design for stack footprints and weights larger than current state-of-the-art

infrastructure investments for campus improvements (water